

				PROBABILITY		CONSEQUENCE						
Contract:		SA Rail		Likelihood		Minor (1)	Moderate (2)	Serious (3)	Major (4)	Catastrophic (5)		
Site/Project:		Cleaning of Assets – Concourse / Maintenance Technician		Common or repeating occurrence	Almost Certain (5)	Medium 11	High 16	Extreme 20	Extreme 23	Extreme 25		
Work Area:		Concourse		Known to occur, or, "it has happened"	Likely (4)	Low 7	Medium 12	High 17	Extreme 21	Extreme 24		
Name:		Simon White	Signature	Could occur	Possible (3)	Low 4	Medium 9	Medium 13	High 18	Extreme 22		
Position:		National Project Manager - 0450 251 778		Date	Not likely to occur	Unlikely (2)	Low 2	Low 5	Medium 10	Medium 14	High 19	
Revision Details:		Rev No.:	1	Rev Date:	01/05/2023	Practically Impossible	Rare (1)	Low 1	Low 3	Low 6	Low 8	Medium 15

1. IDENTIFY THE JOB STEPS		2. ID THE HAZARDS	3. ASSESS RISK	4. ENGAGE RISK CONTROLS	5. RESIDUAL RISK	6. RESPONSIBILITY
STEP	JOB STEP	HAZARDS IDENTIFIED	RATING ABOVE	CONTROL MEASURES	RATING ABOVE	POSITION / TITLE
1.	Drugs and Alcohol	Worker affected by Drugs or Alcohol – Injury – risk of injury	20	<ul style="list-style-type: none"> ZERO Tolerance for all workers on JCDecaux sites Random drug/ alcohol Testing Site inspections 	13	All Workers
2.	Fatigue	Incidents as a result of fatigue symptoms	20	<ul style="list-style-type: none"> 12-hour break between work shifts Monitor signs of fatigue as per Contractor and Field Staff Handbook Refer ARA POL021 Fatigue Management Policy Task rotations / rest breaks 	13	All Workers
3.	Working Outdoors	Adverse weather conditions – risk of injury	20	<ul style="list-style-type: none"> Preferable not to conduct work in adverse weather conditions. Always monitor the environment and if conditions change stop work Review SWMS to see if changes to work methods required Use PPE appropriate for weather conditions, i.e. Sunscreen, hats, hi-vis uniform, wet weather gear Heat - Drink plenty of water 	13	All Workers
		Nature danger – risk of injury or death	21	<ul style="list-style-type: none"> Use appropriate PPE - gloves, boots First aid kit and working mobile phone in case of emergency Check for presence of spider webs etc. prior to commencing work, use repellent if present 	13	
4.	Working at nights	Working at nights - personnel-altercations, assaults, etc.	18	<ul style="list-style-type: none"> Do not engage in altercations, go to the next site and return to site when safe to do so Follow SA Rail Step-Back policy and seek a safe place. Visually check your surroundings to ensure that there are no hazards or risks 	4	All Workers

1. IDENTIFY THE JOB STEPS		2. ID THE HAZARDS	3. ASSESS RISK	4. ENGAGE RISK CONTROLS	5. RESIDUAL RISK	6. RESPONSIBILITY
STEP	JOB STEP	HAZARDS IDENTIFIED	RATING ABOVE	CONTROL MEASURES	RATING ABOVE	POSITION / TITLE
				<ul style="list-style-type: none"> Ensure the worksite is adequately lit prior commencing works and throughout the shift 		
5.	Risk Assessment	<p>Risk Assessment not carried out and SWMS not used. – risk of accident to Worker while carrying out work duties</p> <p>Work Area hazards</p>	<p>18</p> <p>13</p>	<ul style="list-style-type: none"> Risk Assessment must be completed for each site. Worker must sign, date and list panels installed on the site Carry out RISK ASSESSMENT of the site – e-copy on One Drive (Risk Assessment are file by the Worker and made available on request) 	<p>4</p> <p>4</p>	All Workers
6.	Incident Reporting	Injury / near miss	9	<ul style="list-style-type: none"> Report any incidents / near misses must be reported within 24 Hours - Rail Operations Centre number to 08 7201 5001 Report any serious incidents via phone to supervisor / project manager Follow process in Incident Report Procedure for all incidents and near misses Report to the - Rail Operations Centre number to 08 7201 5001 immediately Joint investigation between ARA, JCD and SA Rail encouraged 	16	All Workers
7.	Park vehicle	Vehicle accident / Hitting pedestrians/Traffic and bumping into pedestrians	13	<ul style="list-style-type: none"> Wear appropriate PPE prior commencement of works (Hi-Vis, Safety Shoes) Set up appropriate pedestrian/traffic management: Pedestrian and traffic management, Drive safely, use roof beacon and hazard lights and be aware of surroundings Check if any Trains/vehicles are approaching If safe, park within designed parking area Beacon lighting must be on at all times when the work vehicle is stationary Drive safely i.e. follow road rules and ensure to activate hazard beacon lighting when required and current driver's license, Wear seat belts Be aware of surroundings at all times and follow all SWMS for appropriate tasks at hand Ensure speed limits are maintained at all times 	1	All Workers
8.	Walking around Train concourse	Slip, trip and fall Sustain serious injury from fall Muscle sprains and stains Pits	13	<ul style="list-style-type: none"> Maintain correct posture while performing works Use the designated pathways / walkways Wear appropriate PPE prior commencement of works (Hi-Vis, Safety Shoes, Gloves, Brim hats etc.) Visually check your surroundings to ensure that there are no hazards or risks – i.e. Pits, Public DO NOT proceed with work if it is not safe to do so – Contact Manger Incident/fault reporting - Rail Operations Centre number to 08 7201 5001 	4	All Workers
9.	Unloading equipment	<p>Danger to Pedestrians – injury to pedestrians</p> <p>Manual Handling – injury while lifting</p>	<p>9</p> <p>13</p>	<ul style="list-style-type: none"> Use of expandable barricades & set up around asset No equipment to be left on footpath or where a trip hazard could be caused to pedestrians Move vehicle after unloading to a safe location Team lifting as required transporting equipment to minimise manual handling strain. 	<p>4</p> <p>4</p>	All Workers

1. IDENTIFY THE JOB STEPS		2. ID THE HAZARDS	3. ASSESS RISK	4. ENGAGE RISK CONTROLS	5. RESIDUAL RISK	6. RESPONSIBILITY
STEP	JOB STEP	HAZARDS IDENTIFIED	RATING ABOVE	CONTROL MEASURES	RATING ABOVE	POSITION / TITLE
10.	Accessing sites	Not being accounted for in the event of an emergency – risk of injury	13	<ul style="list-style-type: none"> Wear approved PPE Gear on entering JCDecaux sites / SA Rail Sites Carry required identification (White Card, RIW & JCDecaux ID) SIGN IN with relevant SA Rail personnel 	9	All Workers
		Unfamiliar work environment– risk of injury	18		<ul style="list-style-type: none"> Worker to carry Valid copy of SWMS for the site Complete any other required site-specific induction Wear Transport issued lanyard after being inducted on site by the Officer in Charge and return at the end of your shift. 	
11.	Transporting Equipment to work site/area	Pedestrians	12	<ul style="list-style-type: none"> Give way to all pedestrians Team lifting as required transporting equipment to minimise manual handling strain. 	4	All Workers
		Manual Handling	13		4	
12.	Preparing the work site/area	Pedestrians hazards	13	<ul style="list-style-type: none"> Be aware of Pedestrians and used barricades or witches' hats Report contaminated needles DO NOT HANDLE UNLESS ABSOLUTELY NECESSARY Mobile phones are to be on appropriate volume Headphones are banned from JCDecaux sites All infrastructure damage to be reported immediately Check that the lighting is adequate and operating correctly, if NOT mark on the Risk Assessment Form Stop work and speak to supervisor regarding lighting 	9	All Workers
		Contaminated needles – injury by needle or contents of syringe	9		15	
		Mobile phones, headphones can cause distractions resulting in injury	8		16	
		Infrastructure Damage	11		16	
13.	Damage to Assets	Insufficient lighting – risk of injury	11	<ul style="list-style-type: none"> Report to supervisor, do not undertake works if exposed electrical wires present Barricade site off with expandable barrier 	16	All Workers
		Exposed electrical / sharp edges or broken glass	13		9	
14.	Cleaning Assets (wipe down all surfaces and glass)	Slips / Trips	9	<ul style="list-style-type: none"> Use of spray bottles in order to minimise water usage Ensure chemicals are labelled and familiar with SDS Use of correct PPE fit for purpose Use insect spray/repellent wear PPE Be aware of surroundings 	4	All Workers
		Chemical injury	17		9	
		Insects and Spiders	13		9	
		Hazards to Pedestrians	5		2	

1. IDENTIFY THE JOB STEPS		2. ID THE HAZARDS	3. ASSESS RISK	4. ENGAGE RISK CONTROLS	5. RESIDUAL RISK	6. RESPONSIBILITY
STEP	JOB STEP	HAZARDS IDENTIFIED	RATING ABOVE	CONTROL MEASURES	RATING ABOVE	POSITION / TITLE
		Manual Handling	13	<ul style="list-style-type: none"> Use correct manual handling techniques maintain good posture bend knees 	4	
		Overreaching for cleaning the top of asset	13	<ul style="list-style-type: none"> Utilise safety step to reach top of asset, Maintain stable footing 	9	

ADDITIONAL REQUIREMENTS				
TRAINING REQUIRED	TOOLS/EQUIPMENT/PPE REQUIRED		LICENCES/PERMITS/APPROVALS REQUIRED	EQUIPMENT/MAINTENANCE CHECKS REQUIRED
Correct posture and movement to handle equipment and conduct this task	Safety signs/Barricades	Approved chemical	Contract Specific Inductions	
Chemical handling training	Refer operational folder for SDS documents: JD Glance – Non Hazardous Shield Citrus – Non Hazardous Goodbye Graffiti – hazardous and dangerous	Backpack		
Trains safety awareness	Tongs to pick up sharps			
How to wear correct PPE	Microfiber cloths			
	Hi-Vis Uniform (closed up, no red or green), Safety Boots (lace up), Gloves, Safety glasses, Sunscreen, Brim hats, Mask, Long sleeve shirts and trousers			

								
Gloves	Face mask	Eye protection	Hi-Vis Clothing	Appropriate footwear	Hearing protection	Protective clothing	Brim Hats	Sunscreen
<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

Injury &/or Emergency Response

Injury	<ul style="list-style-type: none"> In the first instance, provide medical assistance to the injured worker & contact the ARA Supervisor / CRM.
Emergency	<ul style="list-style-type: none"> Follow the site Emergency Response procedure as directed by site operator. The ARA Incident Response & Reporting Procedure will then be implemented

5. SWMS CONSULTATION

The following companies / contractors participated in the development of this SWMS and agreed on the control measures to reduce the risk

NAME	DATE	POSITION	Company	NAME	DATE	POSITION	SIGNATURE
1. Simon White	28/03/2023	National Project Manager	ARA	5.			
2. Kaveesha Mahanama	28/03/2023	People and Safety Advisor	ARA	6.			
3. Jennifer Stanton	30/01//2021	Technician	ARA	7.			

SWMS SIGN OFF

Person(s) responsible for supervising/inspecting work to sign. Cleaners to sign when they have read, understood, is competent to do this task safely and agrees with the SWMS

NAME	DATE	POSITION	SIGNATURE	NAME	DATE	POSITION	SIGNATURE
1.				11.			

2.				12.			
3.				13.			
4.				14.			
5.				15.			
6.				16.			
7.				17.			
8.				18.			
9.				19.			
10.				20.			

6. APPROVAL

To be signed by the FM or delegate once all fields of this form have been completed and all hazards have been eliminated or reduced as low as reasonably practicable.

NAME	DATE	POSITION	SIGNATURE

7. LEGISLATION / REGULATIONS REFERENCE



Safe Work Method Statement (AUS) / Job Hazard Analysis (NZ)



Address: 442-450 Auburn Road, Hawthorn, VIC, 3122 | 1300 889 210
ARA Property Services Pty Ltd | ABN: 99 160 762 433

SA:
Work Health and Safety Act 2012
Work Health and Safety Regulation 2012

8. CHANGE REGISTER			Expiry
Revision Number	Date	Change	Expiry
1	May 2023	Creation of SWMS	April 2025